


15-163-02808-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rooks County, Sec. 9 Twp. 9 Rge. 17 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SE NW
Lease Owner Southern States Oil Co.
Lease Name Mainquist #1 Well No.
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6/6/79 19
Plugging completed 6/12/79 19
Reason for abandonment of well or producing formation
depleted.
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Schmidt
Producing formation Depth to top Bottom Total Depth of Well 3621
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	182	none
				5-1/2	3535	506'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Sanded to 3500' and ran 5 sacks cement. Loaded hole with salt water, shot pipe at
2508', 2010', 1516', 1024', 928', 800', 704', 608', 507', pulled 16 joints. Pumped
130 sacks 50-50 pos, 6% gel, 15 sacks gel, 1 sack hulls and 8-5/8 plug.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KESLO CASING PULLING
CHASE, KANSAS

RECEIVED
6/18/79
JUN 18 1979


STATE OF KANSAS COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of June, 19 79

Margaret Melcher
Notary Public.

My commission expires



15-163-02808-00-01

WELL LOG

GEORGE OIL COMPANY
WARRANT NO. 1
SE SE NW 9-98-17N
COOKE COUNTY, KANSAS

WASH DOWN
Elevation 2400' ND
6-5/8" Surface pipe to 192' W/175' BOP
in original hole
5 1/2" Oil String to 3539' W/175' BOP

Rotary
Commenced April 29, 1959
Completed April 26, 1959
Final Completion Oct. 27, 1959
Initial Production 250bbls Est.

Deepening Well in Arbuckle

Old Total Depth 3530'
Deepened to 3621'
S. D. 3621'

Original Well Drilled by George Oil & Gas Co., Inc.

RECEIVED
STATE CORPORATION COMMISSION

MAR - 6 1979

CONSERVATION DIVISION
Wichita, Kansas

3/6/79