


STATE CORPORATION COMMISSION

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

15-443-04131-0020
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
 Section Plat

Rooks County. Sec. 9 Twp. 9 Rge. 17 (E) W (W)
 Location as "NE/CNW%SW%" or footage from lines SE SE SW
 Lease Owner Morgenstern & Specter, Inc.
 Lease Name Fike Well No. 1
 Office Address Russell, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) oil
 Date well completed 8-12-60 19
 Application for plugging filed 12-25-61 19
 Application for plugging approved 12-27-61 19
 Plugging commenced 2-16-62 19
 Plugging completed 2-22-62 19
 Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
 Producing formation arbuckle Depth to top 3485 Bottom 3534 Total Depth of Well 3535 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	202'	None
				4-1/2"	3534'	2735'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3535', sanded to 3520' and dumped 4 sacks of cement @ 3520' with dump bailer. Pulled 74 jts. of 4 1/2" casing and circulated with jell mud and pumped in 20 sacks of cement @ 550'. Pulled 4 1/2" to 170' and pumped in 20 ~~sacks~~ sacks of cement @ 170'. Pulled balance of 4 1/2" casing, bailed mud and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE

3/12/62
RECEIVED
 STATE CORPORATION COMMISSION
 MAR 12 1962
 CONSERVATION DIVISION
 WICHITA

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
 Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 1962

My commission expires May 20, 1964 Milton J. Volue Notary Public.



15-163-04131-00-00

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MORRIS VEVERKA
Farm- Fike No. 1

SEC. 9 T. 9 R. 17W
SE NE SW

Total Depth. 3535'
Comm. 7-20-60 Comp. 8-12-60
Shot or Treated.
Contractor. A. L. Jackson
Issued. 3-11-61

County Rocks
KANSAS



CASING:
8" 202'
5" 3534'

Elevation. 2063' RB

Production. 32 BOPD

Figures Indicate Bottom of Formations.

surface clay, post rock	70
shale	500
sand	625
shale & shells	765
shale, sand, shells	1315
shale, red bed	1345
Anhydrite	1375
shale	1830
lime	1845
lime & shale	2325
lime	2390
shale & lime	2720
shale	2745
shale & lime	2850
shale	2955
Broken lime	3060
lime & shale	3175
lime	3180
shale & lime	3215
Lansing	3255
lime	3350
lime & shale	3378
lime	3442
lime & sand	3470
lime	3535
Total Depth	

TOPS:

Anhydrite	1345
Topeka (scout)	2949
Heebner (scout)	3159
Toronto (scout)	3190
Kansas City	3210
Base Kansas City (scout)	3439
Arbuckle	3485

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1961

CONSERVATION DIVISION
Wichita, Kansas

12/27/61