

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

15-163-21182-00-00

COUNTY Rooks SEC. 9 TWP. 9S RGE. 17W E/W  
 Location as in quarters or footage from lines:  
NE SE NW


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Green & Green  
 Lease Name Mainquist #1 Well No. \_\_\_\_\_  
 Office Address P.O. Box 503 Hays, Kansas 67601  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 5-8-82  
 Plugging completed 5-13-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_  
Depleted

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3580'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	264'	none
				5-1/2"	3576'	2535'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Pushed bottom plug at 3100', ran 50' of sand and 5 sacks cement. Shot casing  
@2627' and 2542'. Pulled a total of 59 joints of 5-1/2" casing. Plugged well with  
4 sacks hulls, 12 sacks gel, 70 sacks cement, 4 sacks gel, 8-5/8" plug, 70 sacks  
cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 176 Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 82



My Commission expires: \_\_\_\_\_

Irene Hoover  
 STATE CORPORATION COMMISSION  
 RECEIVED  
 5/20/82

MAY 20 1982

CONSERVATION DIVISION  
 Wichita Kansas