

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas. 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-04139-00-07

API NUMBER WELL DRLED IN 1937

LEASE NAME Robert J. McClay

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #2

Ft. from S Section Line

Ft. from E Section Line

SEC. 12 TWP. 9S RGE. 17W (E) or (W)

COUNTY Rooks

Date Well Completed 12-14-37

Plugging Commenced 8/29/85

Plugging Completed 9/3/85

LEASE OPERATOR ARCO Oil and Gas Company

ADDRESS Box 3708, Enid, Oklahoma 73702

PHONE# (405) 233-6800 OPERATORS LICENSE NO. 5398

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Contacted KCC in Wichita for emergency plugging per-

mission. Is ACO-1 filed? If not, is well log attached?

Producing Formation Lansing-Kansas City Depth to Top 3139' Bottom 3333' T.D. 3333'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing & Kans. City	oil & water	105	0	10 3/4	105	none
		3154	0	700" 20#	3154	none
		3313	3115	6 5 1/2'	1991	none
		1022	0	5 1/2" OD liner	1022'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mixed and pmpd 100 sx reg w/ 3% CaCl. Pull 4 jts. Mix & pmpd 220 sx reg. w/ 3% CaCl. 8-30 Tag top cmt @ 3225'. RIH w/ 2 3/8" OD tbg. Pump 8 sx. hulls. Mix & pmp 150 sx. 50/50 POZ. Wait 2 hrs. Tag cmt @ 3015. Mix & pmp 150 sx. 50/50 POZ w/ 8 sx hulls. POH. 9-3-85- Tag top cmt @ 2130'. RIH w/ 2 3/8" OD tbg to 2100'. Mix and pmp 150 sx 50/50 POZ. POH. Tag top cmt @ 1250' (If additional description is necessary, use BACK of this form.)

(OVER)

Name of Plugging Contractor Ostrom Well Service, Inc. License No. 5680

Address 1012 W. Mill, Plainville, Kansas

STATE OF Rooks COUNTY OF Kansas, ss.

Robert L. McGlinn

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert L. McGlinn

(Address) Box 849, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 13 day of September, 19 85

My Commission Expires: August, 1988

Notarized  
STATE CORPORATION COMMISSION

SEP 17 1985

Form CP-4  
Revised 08-84

CONSERVATION DIVISION

RIH w/ 2 3/8" OD tbg. to 2100'. Mix and pmp 150 sx 50/50 POZ. POH. Tag top cmt @ 1250'. RIH 1085'. Pump 10 sx hulls 130 sx cmt. Good circ. to surface. Circ cmt to surface w/ 125 sx, circ 10 sx to pit. Dug out cellar to 10 3/4" surface. Hooked up to 7" OD and 5 1/2" annulus. Mix and pmp 130 sx 50/50 POZ cmt falling. Ordered cmt. Cut off 10 3/4" OD csg., 7" OD csg., 5 1/2" csg. Weld on plate w/ 2" collar. Hook up in cellar. Mix and pmp 150 sx 50/50 POZ w/ hulls. Shutdown w/ 100# standing pressure. Rig Down. Cmt @ 2" collar. Well plug and abandon @ 6:30 P.M. 9/3/85.  
(K.C.C. Carl Woodrow was on location while plugging.)