

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

19245
15-163-~~01012~~-0000
WELL PLUGGING RECORD

County, Sec. 12 Twp. 9S Rge. 17W (~~E~~) (W)

Well No....2

19...

19...

19...

19...

19...

• • • • •

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Show depth and thickness of all water, oil and gas formations.

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Cemented with 10 Sacks cement 35' to 0'

7/10/51
RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Alkay Oil Company

Address.....929 Kennedy Building - Tulsa, Oklahoma

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
E. G. Moshlenkamp, Office Manager (employee of owner) or (owner of _____)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN to before me this 10th day of September 195

My commission expires March 8, 1954

Notary Public.

22-5133-s

9-48-10M

PLUGGING

WELL LOG

15-163 - ~~01012~~ 19245 - 00-00

ALKAY OIL COMPANY
LEO W. HRABE No. 2
SW SE NE 12-9S-17W
Rocks County, Kansas

Elevation 1996' K. B.
All Measurements from K. B.

Commenced: August 17, 1951
Completed: August 30, 1951

CASING RECORD:
8 5/8" at 164' with 150 Sacks cement

FROM	TO	
0	50	Surface Clay
50	67	Sand
67	167	Shale & Shells
167	1264	Shale & Shells - Red Bed
1264	1296	Anhydrite
1296	1520	Shale & Shells
1520	1905	Sand & Shale
1905	1935	Lime
1935	2155	Shale & Shells
2155	2250	Shale & Shells
2250	2362	Shale & Lime
2362	2655	Shale & Lime
2655	2725	Shale
2725	2975	Shale & Lime
2975	3065	Lime
3065	3097	Shale & Lime
3097	3435	Lime
3435		TOTAL DEPTH

TOPS:

Anhydrite 1264
Heebner 3091
K. C. 3130
Arbuckle 3423

DRILL STEM TESTS:

3214-38 - Open 45 Minutes - 36' Slightly oil cut watery mud
3262-70 - Open 30 Minutes - 6' Mud
3424-30 - Open 15 Minutes - 5' Mud
3430-35 - Open 1 Hour - 40' Watery Mud.

D&A

9/11/51
STATE OF KANSAS
CORPORATION COMMISSION
SEP 11 1951
REGISTRATION DIVISION
Topeka, Kansas

