

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
67202 TYPE OR PRINT

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-30015 -00 00
LEASE NAME GARVERT Wichita, KS

WELL NUMBER 5

NOTICE: Fill out **completely** 3630 Ft. from S Section Line
and return to Cons. Div. 330 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 6 TWP. 9S RGE. 17W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY ROOKS
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 2/65

Character of Well D&A (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 4/15/03
Plugging Completed 4/15/03

RECEIVED
MAY 12 2003
KCC WICHITA

The plugging proposal was approved on 4/15/03 (date)
by Rich Williams w/KCC Hays, KS. (KCC District Agent's Name)

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation LKC Depth to Top 3111 Bottom 3335OA TD 3409 PBTD3357

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	218	8 5/8	218	0
		production	3406	5 1/2	3406	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: RIH w/2 7/8" tbg to 2933'. Tied onto 2 7/8 tbg. Pumped 30 sxs SMD cement. Pumped 60 sxs SMD cement w/400# hulls. Pulled tbg to 1290'. Pumped 75 sxs & 100# hulls to circulate cmt to sur. TOH w/tbg. Tied onto 5 1/2" csg. Pumped 10 sxs 350# max press. 300# ISIP. Tied onto 8 5/8. Pumped 35 sxs SMD cement 300# max press. ISIP 100#. Well P/A. Witnessed and approved by Rich Williams w/ KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK .SS.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 16th day of April, 2003

Notary Public - Barbara J. Dodson [Signature]

My Commission Expires: 12/16/03
BARBARA J. DODSON
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 12-16-03

Revised 05-88

[Signature]



CHARGE TO: *Murphy Drly Co.*

ADDRESS:

CITY, STATE, ZIP CODE: *Hill City, Ks*

TICKET No 5242

PAGE 1 OF 1

SERVICE LOCATIONS 1. <i>Hay 16</i>	WELL/PROJECT NO. <i>5</i>	LEASE <i>Garvert</i>	COUNTY/PARISH <i>ROOKS</i>	STATE <i>KS</i>	CITY	DATE <i>4-15-03</i>	OWNER <i>Same</i>
2.	TICKET TYPE <input type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR	RIG NAME/NO. <i>Murphy</i>	SHIPPED VIA <i>105</i>	DELIVERED TO <i>N.E. Plannell</i>	ORDER NO.	
3.	WELL TYPE <i>oil</i>	WELL CATEGORY <i>well abandoned</i>	JOB PURPOSE <i>P.T.A</i>	WELL PERMIT NO.		WELL LOCATION	
4.	REFERRAL LOCATION	INVOICE INSTRUCTIONS					

15-163-30015-0000

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
					MILEAGE						
<i>580</i>					<i>additional HPS Pump 2nd well</i>		<i>3</i>	<i>HRS</i>		<i>100.00</i>	<i>300.00</i>
<i>330</i>					<i>SMD Cement</i>		<i>210</i>	<i>SKS</i>		<i>9.75</i>	<i>2047.50</i>
<i>100</i>					<i>Crew Mileage</i>		<i>30</i>	<i>mi</i>			<i>30.00</i>
<i>275</i>					<i>Hulls</i>		<i>5</i>	<i>SKS</i>		<i>20.00</i>	<i>100.00</i>
<i>581</i>					<i>Bulk Service Charge</i>		<i>210</i>			<i>1.00</i>	<i>210.00</i>
<i>583</i>					<i>Drayage</i>		<i>312</i>	<i>90</i>	<i>T.M.</i>	<i>.85</i>	<i>265.97</i>

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X

DATE SIGNED: *4-15-03*

TIME SIGNED: *9:00*

[Signature]

REMIT PAYMENT TO:

SWIFT SERVICES, INC.

P.O. BOX 466

NESS CITY, KS 67560

785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	<i>2953.47</i>
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	<i>156.53</i>
ARE YOU SATISFIED WITH OUR SERVICE?	<input type="checkbox"/> YES <input type="checkbox"/> NO			TOTAL	<i>3110.00</i>
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR
[Signature]

APPROVAL
[Signature]

Thank You!

5-163-30015-00-00

SWIFT Services, Inc.

JOB LOG

DATE 4-15-03 PAGE NO. 1

CUSTOMER *Murphy Dry Co.*

WELL NO. *5*

LEASE *Garrett*

JOB TYPE *P.T.A.*

TICKET NO. *5242*

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0845							on loc
<i>90 SKS</i>			16 BBC					Tbg at 2933 PER in hole at 305'
			34 BBC					Pump 30 SKS SMD CMT w/o Hulls Pump 60 SKS CMT w/ 400 Hulls w/ 36 BBC Pumped CIRC water To Surf out 5 1/2
								Knock loose Pull Tbg To 1290'
								Hookup at 1290 Pump 75 SKS CMT w/ 100 # Hulls CMT CIRC To Pit
								Pull Tbg out of hole To 5 1/2 w/ 10 SKS CMT PSI to 350 Shut in 300
<i>35 SKS</i>			19 BBC			250		Pump 35 SKS CMT Down 8 5/8 max PSI 300
						100		Shut in 8 5/8 100 PSI
	1230							Job Complete
								210 SKS CMT Total
								500 # Hulls Total