


15-163-02776-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rocks _____ County. Sec. II Twp. 9 Rge. 111 (E) 17 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE.1/4, SE.1/4, NW.1/4
Lease Owner Harbar Drilling Co. Etal
Lease Name Westhusin B Well No. L
Office Address 1019 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole after setting casing
Date well completed November 29, 1948
Application for plugging filed April 30, Verbal
Application for plugging approved April 30, Verbal
Plugging commenced May 1
Plugging completed May 5
Reason for abandonment of well or producing formation Produced water only

If a producing well is abandoned, date of last production None
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Peddy
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3416 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>Surface sands and shales</u>	<u>Surface water</u>	<u>0</u>	<u>90</u>	<u>8 5/8</u> <u>5 1/2"</u>	<u>100'</u> <u>3412</u>	<u>None</u> <u>2537</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Lane Wells plug set in 5 1/2" casing at 3246, Plugged back from top plug to 3203' with crushed rock. Dumped 4 sacks cement in 5 1/2" casing on top rock plugging back from 3203' to 3175'.
Filled hole with heavy mud from top cement (3175) to bottom surface casing (100')
Bridged hole with rock from 100' to 90' with field rock. Dumped 30 sacks cement on top rock filling surface pipe from 90' to top and overflowed in bottom cellar.
Surface casing was cemented from top to bottom on outside at time it was set.
5 1/2" casing was cemented with 100 sacks at time it was set.

5-23-1950

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Harbar Drilling Company
Address 1019 central Bldg., Wichita, Kansas


STATE OF Kansas, COUNTY OF Barton, SS. I, Paul Pfeifer (employee of owner) or owner/operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul Pfeifer

SUBSCRIBED AND SWORN TO before me this 18th day of May, 1950

(Address) Ray Gillis
Notary Public.

My commissior expires 9-4-50



B KCC
2AP

WESTHUSIN B-1

NE 1/4 SE 1/4 NW 1/4 Sec. 11-9S-17W, Rooks County, Kansas

Rigging up Rotary Tools	10-25-48
Tearing down Rotary Tools	11-13-48
Rigging up Cable Tools	11-15-48
Tearing down Cable Tools	11-30-48

Ran 103' of 8 5/8" surface pipe. Set with 65 sacks cement.
 Ran 118 Jts, 3418.53' of 5 1/2" casing. set At 3412' and cemented with 100 sacks cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand and clay	0	100
Sand and shale	100	335
Shale and salt and sand	335	950
Shale, redbed and sand	950	1020
Shale and salt	1020	1230
Salt and shale	1230	1520
Shale and bedbed	1520	1600
Salt and redbed	1600	1720
Shale and shells	1720	1755
Shale	1755	1900
Lime and shale	1900	2946
Lime	2946	3232
Lime and shale	3232	3265
Lime	3265	3375
Lime and shale	3375	3416
Arbuckle	3416	3468 Total Depth

I, Don S. Packer, hereby certify that the above Log is true and correct, to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 31st day of March, 1950

William Kelly

Notary Public

My commission expires: March 22, 1952.

RECEIVED

MAY 23 1950 5-23-1950

PLUGGING
 FILE SEC 11 T 9 R 17 W
 PAGE 4 LINE 27