

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R. 82-3-117

API NUMBER 163 22402-00-00

LEASE NAME Oswald

WELL NUMBER 7

SPOT LOCATION NW SE SW

SEC. 11 TWP. 9 RGE. 17 (XX) or (W)

COUNTY Rooks

Date Well Completed 8-3-84

Plugging Commenced 8-2-84

Plugging Completed 8-3-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558, Garden City, Kansas 67846

PHONE # (316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filled? attached If not, Is well log attached?

Producing formation Arbuckle Depth to top 3430 bottom 3470 T.O. 3470

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	260	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plugged thru drillpipe with a total of 220 sks 50:50 Pozmix 6% gel, 3% CaCl<sub>2</sub> as follows: 25 sks from 3390' to 3280', 25 sks from 1320' to 1210', 100 sks from 800' to 360', 50 sks from 270' to 130', 10 sks from 40' to surface and 10 sks in rat hole. Cement was displaced with mud leaving mud between the plugs. Plugging was completed at 1:30 AM on 8-3-84.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell License No. \_\_\_\_\_  
Address Hays, Kansas \_\_\_\_\_

STATE OF Kansas COUNTY OF Finney, ss.

Millard L. Lindsay (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is true and correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION  
8-27-1984  
AUG 27 1984

(Signature) Millard Lindsay  
(Address) P.O. Box 558, Garden City, Ks.

SUBSCRIBED DIVISION SWORN TO before me this 15th day of August, 1984  
Wichita, Kansas Notary Public

My Commission expires: 6 August 1986