

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-23,135 -00-00

LEASE NAME Westhusin 'B'

WELL NUMBER 13

660 Ft. from S Section Line

2160 Ft. from E Section Line

SEC. 11 TWP. 9S RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed 3/30/91

Plugging Commenced 3/30/91

Plugging Completed 3/30/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Beredco Inc.

ADDRESS 970 Fourth Financial Center, Wichita, KS 67202

PHONE# (316) -265-3311 OPERATORS LICENS. NO. 5147

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/30/91 (date)

by Gibb Scheck (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3474'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	271'	-0-

RECEIVED
STATE CORPORATION COMMISSION
4-4-1991
APR 04 1991
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Mud laden fluid 3474'-3427' 15 sks cement @ 325'
15 sks cement @ 3427' 25 sks cement @ 40'
40 sks cement @ 1300' 15 sks in rathole
100 sks cement @ 800'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Beredco Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 19 91

GLEND A. R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-92

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

Commission Expires: 2-6-92

15-163-23135-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: BBeredco Inc.
970 Fourth Financial Center
Wichita, Kansas 67202

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Westhusin "B" WELL #13

LOCATION: 150' E of W/2 SW SE
Section 11-9S-17W
Rooks County, Kansas

LOGGERS TOTAL DEPTH: 3473'

ROTARY TOTAL DEPTH: 3474'

COMMENCED: 3/20/91

CASING: 8-5/8" @ 271' w/175 sks cement

ELEVATION: 2024' K.B.

COMPLETED: 3/30//91

STATUS: Dry Hole

RECEIVED
STATE CORPORATION COMMISSION
4-4-1991
APR 04 1991
CORPORATION DIVISION
Wichita, Kansas


DEPTHS & FORMATIONS

(All measurements from K.B.)

Dakota Sand	577'	Toronto	3138'
Cedar Hill	888'	Lansing-Kansas City	3155'
Anhydrite	1300'	Base Kansas City	3396'
Topeka	2895'	Arbuckle	3429'
Heebner	3112'	R.T.D.	3474'

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on April 2, 1991.

My commission expires: February 6, 1992.

GLENDAS R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-92


Glenda R. Tiffin, Notary Public