

15-163-19251-00-02

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 9-26-39LEASE NAME WesthusinWELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section LineW/2 SE SE Ft. from E Section LineLEASE OPERATOR Berexco, Inc.ADDRESS Box 723 Hays, Kansas 67601PHONE# 913 628 6101 OPERATORS LICENSE NO. 5363Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SEC. 11 TWP. 9 RGE. 17 (E) COUNTY RooksDate Well Completed 9-26-39 11/5/41Plugging Commenced 5-13-92Plugging Completed 5-19-92The plugging proposal was approved on 5-19-92 (date)by Dennis Hamel (KCC District Agent's Name).Is ACO-1 filled? If not, is well log attached? Producing Formation Depth to Top Bottom T.D. 3133

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Casing	0	3165	7		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perf. 2 shot at 1290' + 800'. Run tubing to 1282.54. Mix 300 sk. 60/40 pos, 10% gel, 1/4# flow seal, 500# hulls. Did not circulate. Hook to 7" casing. Mix 150 sk. 60/40 pos, 10% gel, 1/4# flow seal, 500# hulls. Well on vacuum. Openended 150 sks. 60/40 pos, 10% gel, 1/4# flow seal down casing. Perf. 3 shot at 150'. Run 50 sks. 60/40 pos, 8% gel. Hook up to 7". Mix 80 sk. 60/40 pos, 8% gel.
(If additional description is necessary, use BACK of this form.)
Circulated to surface on 7" annulus.

Name of Plugging Contractor Berexco, Inc. License No. 5363Address Box 723 Hays, Kansas 67601NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.STATE OF Kansas COUNTY OF Ellis, ss.Mr. Ted Crawford

(Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford(Address) Box 723 Hays, No. 67601

NOTARY PUBLIC-State of Kansas
ROSEMARY SMITH
My Appt. Exp. 5-1-95
SUBSCRIBED AND SWORN TO before me this 20 day of May, 1992

My Commission Expires: 5-1-95

Notary Public

Form CP-4
Revised 05-88
Wichita Falls