


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 11 Twp. 9 Rge. 17 ~~2E~~ (W)
Location as "NE/CNW/SW" or footage from lines CSE 1/2 of E 1/2 SE 1/2
Lease Owner Plain-Stock Oil & Gas Co.
Lease Name Westhusin Well No. 3
Office Address Plainville, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed January 22, 1942 19
Application for plugging filed May 25, 1953 19
Application for plugging approved May 28, 1953 19
Plugging commenced June 4, 1953 19
Plugging completed June 13, 1953 19
Reason for abandonment of well or producing formation Oil depleted to one barrel per day, Dakota water broke through casing.
If a producing well is abandoned, date of last production May 17, 1953 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty
Producing formation Lansing-Kansas City Depth to top 3154 Bottom 3335 Total Depth of Well 3325 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City-Lansing	Oil	3212	3218	8 5/8	105	None
" " "	Water	3244	3256	5 1/2	3190	1576.66
" " "	Oil	3313	3319	4" liner	155	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Halliburton Bridge Plug	3015
Dakota Sand	3015 to 2987
Mud & 4sacks cement	2987 to 175
Mud	175 to 160
Rock Bridge	160 to 130
15 sacks cement	130 to 30
Mud	30 to 8
Surface dirt	8 to Surface

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Betts Oil Field Service
Address 37 S. Kansas, Russell, Kansas

STATE OF KANSAS, COUNTY OF ROOKS, ss.
C. C. Reeves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. C. Reeves
Plainville, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 53

My commission expires Nov 7, 1956
Letitia A. Freeman Notary Public.



7-17-1953

Westhusin #3

Center of SE $\frac{1}{4}$ of E $\frac{1}{2}$ of SE $\frac{1}{4}$ Section 11, 9S-17W
 Rocks County, Kansas.
 Plain-Stock Oil & Gas Co.
 and
Helmerich & Payne, Inc.

Commenced: December 20, 1941
 Completed: January 22, 1942

Caliche	0	75
Shale	75	108
Shale & shells	108	530
Sand	530	590
Shale & sand	590	770
Sand & lime shells	770	830
Sand	830	845
Sand & shale	845	1035
Anhydrite	1035	1065
Shale & shells	1065	1285
Lime	1285	1320
Broken Lime	1320	1350
Shale, red bed & shells	1350	1500
Shale & shells	1500	1790
Broken Lime	1790	1905
Lime	1905	2420
Broken lime & shale	2420	2472
Broken lime	2472	2870
Lime	2870	2975
Broken lime	2975	3034
Lime	3034	3228
Lime, hard	3228	3236
Lime & shale	3236	3243
Lime	3243	3288
Shale & lime shells	3288	3293
Lime 3293	3293	3332
Shale	3332	3335
Total Depth	3335	

Casing Record

8-5/8" Surface Casing set at 105' and
 cemented with 75 sacks cement

5-1/2" O.D. Casing set at 3190' and
 cemented with 125 sacks of cement.

Copy of Log signed by William Broadhurst for
 Helmerich & Payne, Inc.

PLUGGING
 FILE SEC 11 T 9 R 17W
 BOOK PAGE 104 LINE 4

RECEIVED
 CORP. RECORDS SECTION
 JUL 6 1953
 CONSERVATION DIVISION
 Wichita, Kansas