


15-163-03121-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
816 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

ROOKS County. Sec. LL Twp. 9S Rge. 17 W (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines CNW $\frac{1}{2}$  SE $\frac{1}{2}$   
Lease Owner Plain-Stock Oil & Gas Co.  
Lease Name John R. Westhusin Well No. 4  
Office Address Plainville, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed July 3, 1943 19 43  
Application for plugging filed October 5, 1957 19 57  
Application for plugging approved October 8, 1957 19 57  
Plugging commenced October 8, 1957 19 57  
Plugging completed October 11, 1957 19 57  
Reason for abandonment of well or producing formation Out of fluid  
If a producing well is abandoned, date of last production October 1956 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Kansas City Depth to top 3151 Bottom 3335 Total Depth of Well 3335 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	112	None
				5 1/2	3151	1405
				4"	180	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

Plugged back from 3335' to 3120'  
w/crushed rock, dumped 4 sax cement  
@ 3120' w/dump bailer. Top of Cement  
3095'. Pumped in 15 sax Gal-Mud and  
30 sax cement through 5 1/2" casing @  
650' by Globe Cementing Co. Filled  
hole w/mud to 35'. set rock bridge,  
dumped 10 sax cement for cap.

FILED  
STATE OF KANSAS  
10-17-1957

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Plain-Stock Oil & Gas Co.  
Address Plainville, Kansas. Plugging Contractor, Miller Casing Pulling Co.  
License # 12, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF ROOKS, ss.  
C. C. Reeves (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. C. Reeves  
Plainville, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of October 19 57

My Commission Expires September 28, 1959

My commission expires.....

Helen A. Kiefer  
Notary Public.

PLUGGING  
NOV 11 T 9 R 174  
BOOK PAGE 51 LINE 19

Westhusin #4 15-163-03121-00-00

W/2 SE/4 of Section 11-9S-17W,  
Rooks County, Kansas  
Flainstock Oil & Gas Company  
and  
Helmerich & Payne, Inc.

Commenced: May 31, 1945  
 Completed: July 3, 1945

Surface clay and shale	0	112
Shale and shells	112	550
Shale and sand streaks	550	992
Sand and pyrite	992	1045
Red bed and shale and shells	1045	1278
Anhydrite and lime	1278	1285
Anhydrite	1285	1314
Shale, red bed and shells	1314	1455
Shale and shells	1455	1625
Salt and shells	1625	1720
Shale	1720	1770
Line w/streaks of shale	1770	1960
Broken lime	1960	2145
Lime	2145	2415
Shale	2415	2490
Shale and lime	2490	2600
Broken lime	2600	2790
Broken lime and shale	2790	2860
Line (Top of Topeka 2868)	2860	2900
Line	2900	3115
Line and streaks of shale	3115	3145
Shale and streaks of lime	3145	3151
Lime	3151	3171
Shale	3171	3173
Red shale	3173	3184
Lime	3184	3188
Gray cherty lime	3188	3201
Light brown lime	3201	3207
Line	3207	3215
Gray cherty lime	3215	3228
Lime	3228	3238
White lime	3238	3250
Lime and chert	3250	3258
White lime	3258	3260
Cherty lime	3260	3263
Light gray sandy lime	3263	3268
Line	3268	3280
Shale	3280	3284
Lime, cherty	3284	3286
Pink chert	3286	3288
Lime	3288	3297
Green shale	3297	3300
Hard lime	3300	3304
Line	3304	3320
Hard cherty lime	3320	3327
Soft lime	3327	3330
Brown lime	3330	3335
<b>TOTAL DEPTH</b>	<b>3335</b>	

CASING RECORD

8-5/8" Casing set at 112' and cemented with 60 sacks of cement.

5-1/2" Casing set at 3151' and cemented with 150 sacks of cement.

**PLUGGING**  
 FILE SEC. 11 T. 9 R. 17W  
 BOOK PAGE 51 LINE 19

STATE OF OKLAHOMA )  
 ss  
 COUNTY OF TULSA )

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Westhusin Well #4, located in the West Half of the Southeast Quarter of Section 11, Township 9 South, Range 17 West, Rooks County, Kansas.

HELMERICH & PAYNE, INC.

By William Earl Hunt  
 Treasurer

Subscribed and sworn to before me, a Notary Public, this 27th day of July, 1945.

My commission expires October 18, 1945

C. V. Wilkin  
 Notary Public

~~My commission expires July 22, 1947.~~

OCT 7 1945  
 10-7-1957  
 DIVISION  
 Kansas