


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County. Sec. 11 Twp. 9 S Rge. 17 W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SE SW NE
Lease Owner Francix Oil & Gas, Inc.
Lease Name Westhusin C Well No. 1
Office Address 4120 E 51 th. Tulsa, Okla. 74135
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed January 18 19 54
Application for plugging filed June 9 19 71
Application for plugging approved June 10 19 71
Plugging commenced June 14 19 71
Plugging completed June 14 19 71
Reason for abandonment of well or producing formation Economical reason

If a producing well is abandoned, date of last production May 30 19 71
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Don Truan
Producing formation Lans/ K.C. Depth to top 3102 Bottom 3347 Total Depth of Well 3417 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Tobonto	oil & water	3023	3080	5 1/2" OD	3410	none
Lans/ K.C.	"	3102	3347	"	"	"
Arbuckle	"	3410	3417	"	"	"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Permanent Lane Wells C.I. Bridge plug set at 3310'. Halliburton R4 packer set at 1310' suspended on 2" EUE tubing. Could not pull.
Mix and pump 20 sks. cement, follow with 10 sks. gel, follow with 10 sks. cement down 2" EUE tubing. 1500# maxium pressure.
Mix and pump 10 sks. gel and 40 sks. cement down 5 1/2" casing. 500# maxium pressure.
Mix and pump 40 sks. cement down 8-5/8" OD casing. 400# maxium pressure.

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1971
CONSERVATION DIVISION
Wichita, Kansas
8-20-1971

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Globe Oilwell Cementing Co.
Address P.O. Box 628 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
Robert R. Scott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert R. Scott
Box 791 Hwy, R3 67601
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of Aug, 19 71
Jerome A. Bejart
Notary Public.

My commission expires 2/18/74