

15-163-20061-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 1 1971  
CONSERVATION DIVISION  
Wichita, Kansas

02-01-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Davis Bros.

Complete Address 500 McFarlin Bldg., Tulsa, Oklahoma 74103

Lease Name Mock "A" Well No. 1

Location SE NW NW Sec. 21 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3595'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 4 P Day 26 Month 1 Year 1970

The above well was plugged as follows:

Total Depth 3595' 8 5/8 csg set at 150' cwc 135 sk.

1 1/2 csg set at 3593' cw 100 sk cmt.

1 1/2 csg PBTD 3580' with perf. (3446-3539')

1 1/2 csg squeezed at 730' W/250 sk cmt. Pres. 1800 lbs.

No Pipe Recovered.

Pumped down annulus ( 8 5/8 - 4 1/2 ) with 50 sk 60-40 poz 2% gel. SI pres. 150 lbs.

Pumped thru 1 1/2 plug container with 50 sk 60-40 poz 2% W/6 sk hulls - 22 sk gel &

water - release plug and pumped 55 sk 60-40 poz 2%. Max. pres. 2000 lbs. SI pres. 2000 lbs

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Mancy  
Well Plugging Supervisor

DATE 2-1-71

INV. NO. 3283-11