

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

APR 24 1972
04-24-1972
CONSERVATION DIVISION
Wichita, Kansas

15-163-20430-00-00

Operator's Full Name Patrick Petroleum Corporation

Complete Address Suite 330, Page Court, 220 W. Douglas Wichita, Kansas

Lease Name Whismar Well No. 1

Location SW SW SE Sec. 25 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3586'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Gabbert - Jones (Rotary)

Address Wichita, Kansas License No.

Operation Completed: Hour 10 P Day 21 Month 4 Year 1972

The above well was plugged as follows:

RTD 3586' 8 5/8 csg set at 208' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel. at 550'

Gunned pits, circulated heavy mud, set cementing plug and displaced 70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 4-27-72
INV. NO. 5627-W