

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-163 - 00630 - 00 - 00

FILE NO. 106-28

LOCATION NE NE SW

SEC. 27 TWP. 10 RGE. 17

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Colby

Operator Trans Era Oil Address Russell, Kans

Field _____ County Rooks

Total Depth ~~x3389~~ 3679 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 182' circulated with cement - 5 1/2" at 3375' with
150 sax cement behind - perforated at 3374' - set plugs at
Lane Wells 3402' - filled with chat to 3360', set 4 sax cement
with dump bailer - pulled 2700' 5 1/2" - filled with mud to 180',
set rock and 15 sax cement, mud to 35', set rock and 10 sax
cement to bottom cellar.

PLUGGING
FILE SEC 27 T 10 R 17W
BOOK PAGE 106 LINE 28

06-22-1953
CONSERVATION DIVISION
WICHITA, KANSAS

District Conservation Agent
Date 6-17-53