

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1966
06-14-1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-163-30175-00-00

Operator's Full Name Bankoff & Leben

Complete Address: Box 2479 Tulsa, Okla.

Lease Name Bice Well No. 1

Location SE NW NE Sec. 27 Twp. 10 Rge. 17 (E) (W) X

County Rooks Total Depth 3685

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling Co.

Address: Great, Bend, Kansas License No. _____

Operation Completed: Hour 1 P Day 13 Month 6 Year 1966

The Above well was plugged as follows:

RTD 3685 8 5/8 set at 189 Ft. cw. 145 sc. cement

Gunned pits, circulated heavy mud, set cementing plug at 540 Ft.

and displaced 25 sax cement thru drill pipe. Heavy mud to 190 Ft. set

cementing plug and displaced 20 sax cement thru drill pipe. Heavy mud

to 40 Ft. set cementing plug, 1/3 sax hulls, and 10 sax cement to base

of cellar. Plugged rat hole with 2 sax cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey
Well Plugging Supervisor

DATE 6/14/66

INV. NO. 3404-w