

P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163 -20,668-00-00 (of this well)

03-31-1977

Operator's Full Name Rains & Williamson Oil Co., Inc.

Complete Address 435 Page Ct., 220 W. Douglas, Wichita, Kansas

Lease Name Hageman Well No. 1

Location SE SW NE Sec. 28 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3600'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 4:50 P Day 28 Month 3 Year 1977

The above well was plugged as follows:

RTD 3600' 8 5/8 csg set 246' vvw 150 sx. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red Massey
Well Plugging Supervisor

DATE 3-31-77

INV. NO. 4884-W