

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20130-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 4 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
10-04-1968

Operator's Full Name Kathol Petroleum, Inc.

Complete Address: 900 Sutton Place Wichita, Kansas

Lease Name Ganoung Well No. 1

Location SW SE SE Sec. 32 Twp. 10 Rge. 17 (E) (W) XX

County Ellis Total Depth 3681

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 10:30A Day 1 Month 10 Year 1968

The Above well was plugged as follows:

RTD 3681' 8 5/8 esg set at 231' cwc. Cmt. Mat. 100 sc 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cmt  
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Boat Massey  
Well Plugging Supervisor

DATE 10/4/68  
INV. NO. 8572-W