

15-163-00726-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1964
06-05-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Green Pipe & Supply
Complete Address: Box 1383 Tulsa, Okla
Lease Name Ridler Well No. 1
Location NW NW SW Sec. 32 Twp. 10 Rge. (E) (W) 17
County Rooks Total Depth 3485
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Bert Self
Address: Hutchinson, Kans License No. 48
Operation Completed: Hour 6PM Day 3 Month 6 Year 64

The Above well, was plugged as follows:

8 5/8" 193' circulated with cement - 5 1/2" 3478' with 125 sax cement -
hole in 5 1/2" -
Sand back to 2900' by sand line measurement - set 4 sax cement with dump
bailer at 2900' - pulled 2500' 5 1/2" to 500', circulated hole with heavy
mud at 500' - displaced 20 sax cement through 5 1/2" at 500', heavy mud
to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35',
set 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/5/64

INV. NO. 9266-11

Signed: [Signature]
Well Plugging Supervisor