

15-163-02996 00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 116-45

LOCATION SW NE NE

SEC. 21 TWP. 8 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 5 Lease Silvers

Operator Aylward Drg Co Address 813 1st Natl Bldg Wichita

Field _____ County Rooks

Total Depth ~~3448~~ 3452 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 163' circulated with cement - 5 1/2" at 3446' with
70 sax cement behind.

Filled with sand to 3430', set 4 sax cement with dump bailer,
pulled 2925' 5 1/2" - Filled hole with heavy mud to 160', set
rock and 10 sax cement - mud to 35', set rock and 10 sax cement
to bottom cellar.

District Conservation Agent

Date 5-17-55

PLUGGING
FILE SEC 21 TWP 8 R 19W
BOOK PAGE 116 LINE 45

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1955
MAY 20 1955
CONSERVATION DIVISION
Wichita, Kansas