

KANSAS

Form CP-3  
Rev. 6-4-68STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORTSTATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORTOCT 30 1978  
10-30-1978  
CONSERVATION DIVISION  
(of this well)J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 163-20648-00-00

Operator's Full Name Bowman Oil Co.Complete Address P. O. Box 37, Codell, Kansas 67630Lease Name Gosser Well No. 1Location 150°E SW SE NW Sec. 23 Twp. 10 Rge. (E) (W) 17County Rooks Total Depth 3700'Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       Other well as hereafter indicated       Plugging Contractor Kelso Casing PullingAddress Box 176, Chase, Kansas License No. 683Operation Completed: Hour 9:30 A Day 27 Month 10 Year 1978

The above well was plugged as follows:

Total Depth 3700' 8 5/8 csg set 250' cwc 200 sk.

4 1/2 csg set 3696' cw 125 sk cem. PFS (3366'-3368')

Set 4 1/2 wood plug at 3300' -poured 10' sd- dumped 3 sk cem W/dump bailer. (3300'-3260')

Cutoff &amp; recovered 2158' of 4 1/2 csg.

Mixed &amp; pumped down 8 5/8 csg with 20 sk cel &amp; water W/200 lbs hulls, followed

with 70 sk 50-50 poz 6% -displaced with 7 sk gel &amp; water -released 8 5/8 plug

&amp; mixed &amp; pumped 70 sk 50-50 poz 6% &amp; shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging SupervisorDATE 10-31-78  
8424.WINV. NO.