

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-06619-00-00
Spot: N2SESE Sec/Twnshp/Rge: 20-12S-17W
990 feet from S Section Line, 660 feet from E Section Line
Lease Name: SCHMEIDLER Well #: 2
County: ELLIS Total Vertical Depth: 3702 feet

Operator License No.: 33636
Op Name: TRIUNITED INVESTORS, LLC
Address: 2149 VIZCAYA CIR
CAMPBELL, CA 95008

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3692	0	w/unknown sxs cmt
SURF	8.625	210	0	w/unknown sxs cmt

120.32

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2007 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOHN FOSE Company: TRIUNITED INVESTORS, LLC Phone: (785) 623-0002

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 600# hulls - 15 sxs gel.
High fluid level.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2007 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Superior Well Service perfed casing at 1850' - 1415' - 850'.
RIH with tubing to 3100'. Allied rigged to tubing - pumped 30 sxs 60/40 pozmix with 200# hulls mixed in.
Pulled tubing to 2800'. Allied rigged to tubing - pumped 15 sxs gel with 150# hulls mixed in.
Pumped 10 sxs 60/40 pozmix behind gel.
Pulled tubing to 1900'. Allied rigged to tubing - pumped 100 sxs cement with 250# hulls mixed in to circulate cement to surface.
Pulled tubing. Rigged to 5 1/2" casing with a swedge - pumped 35 sxs cement.
Max. P.S.I. 400#. S.I.P. 300#.
Rigged to 8 5/8" casing - pumped 5 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3693	3702		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 23 2007
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 10/24/07
INV. NO. 2008060675

Remarks: ALLIED CEMENTING COMPANY-TICKET #25775.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

BURCH DRILLING #2 SCHMIEDLER 20-12-17W
 N2 SE SE
 Contr. BERGMAN DRLG ELLIS County
 E. 2152 RB Comm Comp. 1-6-61 IP 84 BOPD

Tops	Depth	Datum
HEEB	3364	-1212
LANS	3411	-1259
ARB	3691	-1539
TD	3702	-1550

Casing
 8" 210
 5" 3692
 DST 3240-85/1 HR, 400' G, 30' H
 GCM, 60' O & GCM, 120' HO & GCM,
 180' O, BHP 1075-940#/30"
 DST 3693-3702/2 HR, 120' OCM,
 825' O, BHP 1005-810#
 CO TD: BL 5 BOPH/3 HR: FU 2100'
 SCHMIEDLER POOL 0/15 HRS

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS