

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-011-23112-00-00  
Spot: E2SENE Sec/Twnshp/Rge: 10-27S-22E  
2000 feet from N Section Line, 330 feet from E Section Line  
Lease Name: KELLER Well #: 10-42  
County: BOURBON Total Vertical Depth: 737 feet

Operator License No.: 33428  
Op Name: FORT SCOTT METHANE PARTNERS, L  
Address: 2329 W MAIN ST # 301  
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	700	0	
STRL	8.625	20	0	

35.00

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/04/2007 12:00 PM  
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 700' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/04/2007 1:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2' CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 500 PSI. 69 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED  
KCC DISTRICT #3

OCT 10 2007

CHANUTE, KS

CPT

INVOICED  
DATE 10/31/07  
INV. NO. 2008060685

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 25 2007

CONSERVATION DIVISION  
WICHITA, KS

Remarks: SPOT LOCATION ESTABLISHED VIA GPS AS 094.89079W & 37.71256 N.

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

PPT