

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23111-00-00
Spot: NENESE Sec/Twnshp/Rge: 8-27S-22E
2000 feet from S Section Line, 350 feet from E Section Line
Lease Name: KELLER Well #: 8-43
County: BOURBON Total Vertical Depth: 887 feet

Operator License No.: 33428
Op Name: FORT SCOTT METHANE PARTNERS, L
Address: 2329 W MAIN ST # 301
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	883	0	
SURF	8.625	21	0	
T1	2.375	842	842	35.00

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 10/01/2007 10:30 AM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 883' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2007 11:15 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 300 PSI. 81 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
795	798		
740	742		
648	651		
616	618		
600			
576	578		
434	435		
426	429		
414	417		

RECEIVED
KCC DISTRICT #3

INVOICED OCT 8 2007 CPT
DATE 10/31/07
INV. NO. 2008060685 CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 25 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: THE WELLS SPOT LOCATION WAS ESTABLISHED VIA GPS AS KEL 8-43 AT 37.70931 N & 095.01698 W.

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PPT