

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23113-00-00
Spot: S2SWSW Sec/Twnshp/Rge: 10-27S-22E
340 feet from S Section Line, 620 feet from W Section Line
Lease Name: KELLER Well #: 10-24
County: BOURBON Total Vertical Depth: 730 feet

Operator License No.: 33428
Op Name: FORT SCOTT METHANE PARTNERS, L
Address: 2329 W MAIN ST # 301
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	726	0	
SURF	8.625	21	0	
T1	2.375	681	681	

35.00

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 10/01/2007 4:00 PM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9219

Proposed Plugging Method: THIS WELL CONSISTD OF 4 1/2" CASING TO 728' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE/

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2007 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE MIXED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 150 PSI. 69 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
630	632		
625	627		
588	590		
568	570		
470			
440	442		
260	261		
250	253		
238	241		

RECEIVED
KCC DISTRICT #3
OCT 8 2007
CPT

INVOICED
DATE 10/31/07
INV. NO. 2008060685
CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 25 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: THE SPOT LOCATION FOR THIS WELL WAS ESTABLISHED VIA GPS AS KEL1024 AT 37.70483 N & 094.99503 W.

Plugged through: CSG

District: 03

Signed Clayton Titel
(TECHNICIAN)

PPT