

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23118-00-00
Spot: W2NE Sec/Twnshp/Rge: 16-27S-22E
1400 feet from N Section Line, 2000 feet from E Section Line
Lease Name: KELLER Well #: 16-32
County: BOURBON Total Vertical Depth: 737 feet

Operator License No.: 33428
Op Name: FORT SCOTT METHANE PARTNERS, L
Address: 2329 W MAIN ST # 301
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	732	0	
SURF	8.625	22	0	
T1	2.375	686	686	

35.00

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 10/01/2007 3:15 PM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 732' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2007 4:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 300 PSI.

Perfs:

Top	Bot	Thru	Comments
669	671		
656	659		
617	619		
596	598		
442			
410	412		
275	278		
262	265		

RECEIVED
KCC DISTRICT #3

INVOICED
DATE 10/31/07 OCT 8 2007 CPT
INV. NO. 2008060685 CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 25 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: GPS SPOT LOCATIN WAS ESTABLISHED AS KEL 1632 AT 37.69990 N & 095.00445 W.

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PKT