

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23131-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 10-27S-22E
330 feet from S Section Line, 2200 feet from E Section Line
Lease Name: KELLER Well #: 10-34
County: BOURBON Total Vertical Depth: 737 feet

Operator License No.: 33428
Op Name: FORT SCOTT METHANE PARTNERS, L
Address: 2329 W MAIN ST # 301
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	734	0	
SURF	8.625	22	0	
T1	2.375	695	695	

35.00

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 10/02/2007 10:00 AM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9219

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 734' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFCAE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/02/2007 10:45 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 500 PSI. 87 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
664	666		
647	650		
612	614		
591	593		
440			
406	408		
268	270		
257	260		

RECEIVED
KCC DISTRICT #3
OCT 8 2007 CPT
INVOICED
DATE 10/31/07
INV. NO. 2008060685 CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 25 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: LOCATION FOR THIS WELL WAS ESTABLISHED VIA GPS AS KEL10-34 AT 37.70486 N & 094.98717.

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PKT