

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-011-23132-00-00
 Spot: SWSWNW Sec/Twnshp/Rge: 14-27S-22E
2300 feet from N Section Line, 350 feet from W Section Line
 Lease Name: OBRIEN Well #: 14-12
 County: BOURBON Total Vertical Depth: 709 feet

Operator License No.: 33428
 Op Name: FORT SCOTT METHANE PARTNERS, L
 Address: 2329 W MAIN ST # 301
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	704	0	80 SX CMT.
RBP		502		
SURF	8.625	22	0	4 SX CMT.

35.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/03/2007 8:00 AM
 Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
 Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9219

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 704' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
 Date/Time Plugging Completed: 10/03/2007 9:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 600 PSI. 87 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
636	638		
522	524		
437	439		
396	398		
382	384		
324	626		
241	244		
230	232		

RECEIVED
 KCC DISTRICT #3

OCT 10 2007 CRT

CHANUTE, KS

INVOICED
 DATE 10/31/07
 INV. NO. 2008060685

RECEIVED
 KANSAS CORPORATION COMMISSION
 OCT 25 2007
 CONSERVATION DIVISION
 WICHITA, KS

Remarks: SPOT LOCASION ESTABLISHED VIA GPS AS 094.97768 W. & 37.69777N.

Plugged through: CSG

District: 03

Signed Clayton P. Titel
 (TECHNICIAN)

PCT