

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23133-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 15-27S-22E
2300 feet from N Section Line, 2300 feet from E Section Line
Lease Name: OBRIEN Well #: 15-32
County: BOURBON Total Vertical Depth: 745 feet

Operator License No.: 33428
Op Name: FORT SCOTT METHANE PARTNERS, L
Address: 2329 W MAIN ST # 301
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	742	0	
SURF	8.625	22	0	
T1	2.375	647	647	35.00

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 10/03/2007 10:00 AM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE KIPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 742' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 10/03/2007 11:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 600 PSI. 87 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
660	666		
647	650		

INVOICED
DATE 10/31/07
INV. NO. 2008060685

RECEIVED
KCC DISTRICT #3
OCT 10 2007 CPT
CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 25 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: THE LOCATION OF THIS WELL WAS ESTABLISHED VIA GPS AS 094.98685 W & 37.69762 N.

Plugged through: CSG

District: 03

Signed

Clayton P. Titel
(TECHNICIAN)

PKT