

TO: .  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-011-23136-00-00  
Spot: NENESE Sec/Twnshp/Rge: 16-27S-22E  
2300 feet from S Section Line, 340 feet from E Section Line  
Lease Name: WRIGHT Well #: 16-43  
County: BOURBON Total Vertical Depth: 731 feet

Operator License No.: 33428  
Op Name: FORT SCOTT METHANE PARTNERS, L  
Address: 2329 W MAIN ST # 301  
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	723	0	80 SX CMT.
SURF	8.625	22	0	4 SX CMT.

35.00

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/03/2007 11:30 AM  
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 723' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE  
Date/Time Plugging Completed: 10/03/2007 12:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 400PSI. 65 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
648	652		
642	645		

RECEIVED  
KCC DISTRICT #3

OCT 10 2007

CHANUTE, KS

INVOICED

DATE 10/31/07

INV. NO. 2008060685

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 25 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: CSG

District: 03

Signed

*Clayton P. Titel*

(TECHNICIAN)

*PKT*