

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23138-00-00
Spot: SWNESENW Sec/Twnshp/Rge: 15-27S-22E
1900 feet from N Section Line, 2000 feet from W Section Line
Lease Name: GARRETT Well #: 15-22
County: BOURBON Total Vertical Depth: 737 feet

Operator License No.: 33428
Op Name: FORT SCOTT METHANE PARTNERS, L
Address: 2329 W MAIN ST # 301
LITTLETON, CO 80120

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|------------------------|
| PROD | 4.5 | 733 | | 80 SX CMT. |
| RBP | | 450 | 450 | |
| SURF | 8.625 | 22 | 0 | 4 SX CMT. 35-00 |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/02/2007 10:45 AM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9219

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 733' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFCE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/02/2007 11:25 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPE INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 300 PSI. 69 SACKS OF CEMENT WERE PUMPED IINTO THIS WELL.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 656 | 659 | | |
| 640 | 643 | | |
| 602 | 604 | | |
| 582 | 584 | | |
| 467 | 470 | | |
| 261 | 263 | | |
| 255 | 258 | | |
| 244 | 247 | | |

RECEIVED
KCC DISTRICT #3

OCT 8 2007
CHANUTE, KS

CPT

INVOICED
DATE 10/31/07
INV. NO. 2008060685

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 25 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: SPOT LOCATION ESTABLISHED VIA GPS AS GAR15-22 AT 37.70828 N & 094.99261 W.

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PCT