

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23139-00-00
Spot: NWNESESW Sec/Twnshp/Rge: 15-27S-22E
1200 feet from S Section Line, 2200 feet from W Section Line
Lease Name: GARRETT Well #: 15-24
County: BOURBON Total Vertical Depth: 706 feet

Operator License No.: 33428
Op Name: FORT SCOTT METHANE PARTNERS, L
Address: 2329 W MAIN ST # 301
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	706	0	80 SX CMT.
RBP		512	512	
SURF	8.625	22	0	4 SX CMT. <u>35.00</u>

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/02/2007 11:25 AM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 706' THAT HAD BEEN CEMENTED IN FORM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2' CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/02/2007 12:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 400 PSI. 78 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
639	642		
632	634		
598	600		
577	579		
536	538		
391	393		
380	382		
258	260		
246	249		

RECEIVED
KCC DISTRICT #3

OCT 8 2007 CPT

CHANUTE, KS

INVOICED
DATE 10/31/07
INV. NO. 2008060685

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 25 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: SPOT LOCATION ESTABLISHED VIA GPS AS GAR15-24 AT 37.69324 N & 094.99274 W.

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

PKT