

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23140-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 15-27S-22E
1600 feet from S Section Line, 2310 feet from E Section Line
Lease Name: OBRIEN Well #: 15-33
County: BOURBON Total Vertical Depth: 720 feet

Operator License No.: 33428
Op Name: FORT SCOTT METHANE PARTNERS, L
Address: 2329 W MAIN ST # 301
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	716	0	80 SX CMT.
RBP		602	602	
SURF	8.625	22	0	4 SX CMT.

35.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/03/2007 9:00 AM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 716' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 10/03/2007 10:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE MIXED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 700PSI. 84 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
646	649		
635	638		
600	602		
582	588		
580	582		
254	258		
244	247		

RECEIVED
KCC DISTRICT #3

INVOICED
DATE 10/31/07
INV. NO. 2008060685

OCT 10 2007
CHANUTE, KS

CPT

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 25 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: GPS LOCATION OF THIS WELL WAS 094.98678 W & 37.69284 N.

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

PPT