

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-19084-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 27-17S-13W  
990 feet from N Section Line, 990 feet from W Section Line  
Lease Name: CHILDS Well #: 6  
County: BARTON Total Vertical Depth: 3368 feet

Operator License No.: 6170  
Op Name: GLOBE OPERATING, INC.  
Address: PO BOX 12  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3363	0	100 SX
SURF	8.625	512		300 SX

109.46

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/19/2007 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: Ordered 500 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Operator elected all cement plug.  
Fluid level 650' - 800'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/22/2007 9:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

10/19/2007  
Log Tech perfed at 1525' - 825' - 350'.  
Kelso RIH with tubing to 2035'. Copeland rigged to tubing - pumped 200 sxs 60/40 pozmix - 4% gel with 400# hulls. Lost circulation.  
Pulled tubing to 1000'. Copeland rigged to tubing - pumped 250 sxs cement with 200# hulls mixed in - fluids started circulating out 8 5/8" casing - ran out of cement - left set until Monday.  
10/22/2007  
Kelso RIH with tubing to 150' - tagged cement - pumped 25 sxs to circulate cement up 8 5/8".  
Pulled tubing - pressured 8 5/8" with Max. P.S.I. 550#. S.I.P. 450#.  
Rigged to 5 1/2" with a swedge - pumped 25 sxs cement.  
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3363	3368	OH	

**INVOICED**  
DATE 10/31/07  
INV. NO. 2008060687

RECEIVED  
KANSAS CORPORATION COMMISSION  
**OCT 25 2007**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND CEMENTING COMPANY-TICKET #C-32165.

Plugged through: TBG

District: 04

HD.

Signed

*Pat Staab*

(TECHNICIAN)

OCT 23 2007

PAT


STICKLE DRILLING COMPANY #6 CHILDS 27-17-13W  
 SE NW NW  
 Contr. PEEL BROTHERS

E 1895KB Comm. 3/9/63 Comp. 3/28/63 BARTON County  
 IP PMP 25 BOPD, NW/ARB  
 3363 $\frac{1}{2}$ -68

LOG Tops	Depth	Datum
ANH	812	+1083
HEEB	3045	-1150
BR LM	3130	-1235
LANS	3146	-1251
ARB	3360	-1465
RTD	3368	-1473

Casing  
 8" 512/300 SX:  
 5" 3363 $\frac{1}{2}$ :  
 NO TESTS:  
 COTD 3368: SWB 1 BOPD, NW/4  
 HRS, NATL: POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

HO: SINGTON  
  
 GEOL-C.V. SHANK