

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-00344-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 35-24S-2E  
1522 feet from S Section Line, 4999 feet from E Section Line  
Lease Name: EILERT Well #: 9  
County: HARVEY Total Vertical Depth: 2847 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2842		
SURF	8.625	250		

92.53

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/24/2007 10:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: ED NEMNICH / JOE STRUB Company: D & S W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND TO 2,790' & TOP WITH 4 SXS. CEMENT. CIRCULATE CEMENT FROM 300' TO THE SURFACE.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/01/2007 1:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SANDED TO 2,790' & TOPPED WITH 4 SXS. CEMENT. PERFORATED 4 1/2" CASING @ 300'. RAN 2 3/8" TUBING TO 300' & CIRCULATED 150 SXS. CEMENT TO THE SURFACE INSIDE 4 1/2" CASING & IN 8 5/8" X 4 1/2" ANNULUS. 09/26/2007 - CHECKED TOP PLUG & CEMENT DOWN 220' INSIDE 4 1/2" CASING & @ SURFACE IN 8 5/8" X 4 1/2" ANNULUS. 10/01/2007 - RAN TUBING TO 220' & CIRCULATED 70 SXS. CEMENT TO THE SURFACE.

Perfs:

INVOICED  
DATE 10/31/07  
INV. NO. 2008060690

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 25 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENT. INVOICE #32578 & #32426.

Plugged through: TBG

District: 02

Signed Michael R Wilson  
(TECHNICIAN)

*PR*