

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-00345-00-00
Spot: NENWSW Sec/Twnshp/Rge: 35-24S-2E
2252 feet from S Section Line, 4358 feet from E Section Line
Lease Name: EILERT Well #: 11
County: HARVEY Total Vertical Depth: 2858 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2857		55 SX CMT.
SURF	8.625	203		

92.89

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2007 11:30 AM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: ED NEMNICH / JOE STRUB Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND TO 2,790' & TOP WITH 5 SXS. CEMENT. CIRCULATE CEMENT FROM 255' TO THE SURFACE.

Plugging Proposal Received By: MICHAEL WILSON

Witness Type: PARTIAL

Date/Time Plugging Completed: 10/01/2007 2:00 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

SANDED TO 2,790' & TOPPED WITH 5 SXS. CEMENT. PERFORATED 5 1/2" CASING @ 255'. RAN 2 3/8" TUBING TO 270' & CIRCULATED 130 SXS. CEMENT TO THE SURFACE IN 4 1/2" CASING & 8 5/8" X 4 1/2" ANNULUS. 09/27/2007 - CHECKED TOP PLUG - CEMENT DOWN 150' INSIDE 4 1/2" CASING & DOWN 37' IN 8 5/8" X 4 1/2" ANNULUS. 10/01/2007 - RAN TUBING TO 147' INSIDE 4 1/2" CASING & TUBING TO 40' IN 8 5/8" X 4 1/2" ANNULUS. CIRCULATED 30 SXS. CEMENT TO SURFACE INSIDE & OUTSIDE OF 4 1/2" CASING.

INVOICED
DATE 10/31/07
INV. NO. 2008060690

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 25 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENT. INVOICE #32579 & #32427.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

PK