

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-19762-00-00
Spot: N2SWSENE Sec/Twnshp/Rge: 15-21S-20E
3265 feet from S Section Line, 990 feet from E Section Line
Lease Name: WARE Well #: F-10
County: ANDERSON Total Vertical Depth: 853 feet

Operator License No.: 3728
Op Name: KENT, ROGER DBA R J ENTERPRISES
Address: 1203 E 4TH AVE
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	823	0	
SURF	6.825	8	0	

35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2007 8:00 AM
Plug Co. License No.: 3728 Plug Co. Name: KENT, ROGER DBA R J ENTERPRISES
Proposal Rcvd. from: ROGER KENT Company: KENT, ROGER DBA R J ENTERPRIS Phone: (785) 448-6995

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 823' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 4 1/2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: PARTIAL
Date/Time Plugging Completed: 03/12/2007 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 825'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 46 SACKS OF CEMENT WERE PUMPED INTO THIS WELL

Perfs:

RECEIVED
KCC DISTRICT #3

OCT 22 2007 CPT

CHANUTE, KS

INVOICED
DATE 10/31/07
INV. NO. 2008060691

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 25 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)