

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-20402-00-00  
Spot: N2SWSWNE Sec/Twnshp/Rge: 15-21S-20E  
3070 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: WARE Well #: E-12  
County: ANDERSON Total Vertical Depth: 869 feet

Operator License No.: 3728  
Op Name: KENT, ROGER DBA R J ENTERPRISES  
Address: 1203 E 4TH AVE  
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	869	0	
SURF	7	20	0	

35.00

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/14/2007 8:00 AM  
Plug Co. License No.: 3728 Plug Co. Name: KENT, ROGER DBA R J ENTERPRISES  
Proposal Rcvd. from: ROGER KENT Company: KENT, ROGER DBA R J ENTERPRIS Phone: (785) 448-6995

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CCASING TO 869' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE  
Date/Time Plugging Completed: 03/14/2007 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE CEMENT PUMP WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 150 PSI. 60 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED  
KCC DISTRICT #3

OCT 22 2007 CPT

CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
825	850		

INVOICED

DATE 10/31/07  
INV. NO. 2008060691

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 25 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: CSG

District: 03

Signed

*Clayton P. Titel*

(TECHNICIAN)

PPT