

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-16124-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 27-17S-13W  
2310 feet from N Section Line, 990 feet from W Section Line  
Lease Name: CHILDS A Well #: 3  
County: BARTON Total Vertical Depth: 3408 feet

Operator License No.: 6170  
Op Name: GLOBE OPERATING, INC.  
Address: PO BOX 12  
GREAT BEND, KS 67530

| String | Size  | Depth (ft) | Pulled (ft) | Comments                        |
|--------|-------|------------|-------------|---------------------------------|
| PROD   | 5.5   | 3398       | 0           | 100 SX                          |
| SURF   | 8.625 | 364        | 0           | w/unknown sxs cmt <u>110.76</u> |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/23/2007 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: Ordered 675 sxs 60/40 pozmix - 4% gel - 800# hulls.  
Operator elected to use all cement plug.  
Low fluid level.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/23/2007 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech perfed at 1535' - 825' - 400'.  
Copeland rigged to 5 1/2" casing with a swedge - pumped 675 sxs 60/40 pozmix - 4% gel with 800# hulls mixed in to circulate cement up 8 5/8" casing.  
Shut in 8 5/8". Max. P.S.I. 400#. S.I.P. 350#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3398 | 3408 | OH   |          |

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 29 2007  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 11-1-07  
INV. NO. 2008060696

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #C-32170.

Plugged through: CSG

District: 04

Signed [Signature]  
(TECHNICIAN)

OCT 24 2007

HARWOOD OIL COMPANY #3 CHILDS A 27-17-13W  
 SE SW NW  
 Contr. MORRISON DRILLING COMPANY BARTON County  
 E 1926 Comm. 11-1-48 Comp. 12-10-48 IP 400 BOPD PHY POT

| Tops | Depth | Datum |
|------|-------|-------|
| ANK  | 813   | +1113 |
| TCP  | 2757  | -831  |
| HCEB | 3075  | -1149 |
| LONS | 3161  | -1235 |
| ASB  | 3396  | -1470 |
| T.C. | 3408  | -1482 |

Casing:  
 8" 364 ACID 500  
 5" 3398 1/2 SWB 20 BOPD HRS

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

