

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Daystar Petroleum, Inc.
Address: Box 360 Valley Center, Ks. 67147-0360
Phone: (316) 755-3492 Operator License #: 30931
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Mike Wilson (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-079-20,622-00-01
Lease Name: Ediger A
Well Number: 1
Spot Location (OOQQ): N/2 SE SE
3630 Feet from North / South Section Line **KCC**
550 Feet from East / West Section Line **PRT**
Sec. 21 Twp. 22 S. R. 03 East West
County: Harvey
Date Well Completed: _____
Plugging Commenced: 10-10-07
Plugging Completed: 10-15-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	278'	None
				5-1/2"	3826'	2014'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3120' and 5 sxs. cement. Cut casing loose @2014', pulled up to 544', pumped 21 sxs. of bentonite w/35 sxs. cement. pulled up to 341', pumped 160 sxs. cement w/300# hulls and circulated to surface, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Daystar Petroleum, Inc.
State of Kansas County, Rice ss.

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 01 2007

Mike Kelso (Employee of Operator) or (Operator) on above described well being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 29th day of October 2007

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PK