

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-195-22483-0000
LEASE NAME Brenner Trust
WELL NUMBER 1-11

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1600' Ft. from South Line of Section
580' Ft. from East Line of Section

LEASE OPERATOR American Energies Corporation 5399 SPOT LOCATION SE SW NE SE
ADDRESS 155 N Market, Suite 710 Section 11 Township 15S Range 21W
CITY, STATE, ZIP Wichita, KS 67202 County Trego
PHONE # 316-263-5785 Date Well Completed 10/11/07
Character of Well D & A Date Plugging Commenced 10/11/07
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 10/11/07

The plugging proposal was approved on 10/11/07
by Herb Deines - District #4 - KCC (KCC District Agent's Name)
Is ACO-1 Filed? Attached If not, is well log attached? Attached
Producing Formation(s) Cherokee - Target Formation Depth to Top 3901 Bottom 3965 T.D. 3965
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface	Water sands	220'	0'	8 5/8" 23#	220'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

1st plug @ 1440' with 25 sx, 2nd plug @ 620' with 100 sx, 3rd plug @ 270' with 40 sx, 4th plug @ 40' with 10 sx,
15 sx in rathole, no mousehole. Used a total of 190 sx 60/40 poz, 4% gel, 1/4# Floseal per sx.
Plug down at 9:45 a.m. Quality Cementing - ticket #1641.

Name of Plugging Contractor Quality Cementing - Mallard J.V. Inc
License No. Unknwn 4958
Address P.O. Box 32 City: Russell State: Kansas Zip 67665
KCC PKT PER CPA/3

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Energies Corporation (Operator)


STATE OF KANSAS COUNTY OF Sedgwick, ss.

Alan L. DeGood, President (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) Alan L. DeGood
(Alan L. DeGood, President, American Energies Corporation)

(Address) 155 North Market, Suite 710 City: Wichita State: Kansas Zip 67202

SUBSCRIBED AND SWORN TO me this 24th day of October 2007



Melinda S. Wooten
Melinda S. Wooten, Notary Public

My Commission Expires: 3/12/08

Form CP-4
Revised 12-92

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 30 2007

CONSERVATION DIVISION
WICHITA, KS

PKT