

10-1

219
R

6-031587

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-02915-00-00

SW NW NW /4 SEC. 17, 9 S, 21 W
4290 feet from S section line
4950 feet from E section line

Operator license# 5565

Lease Cooley well # B-9

Operator: N.C.R.A.

County Graham

Address: 2000 S. Main Street
P.O. Box 1404
McPherson, Kansas 67460

Well total depth 3806 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe B 5/8 Inch @ 174 feet

123.69

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 1 Month: October Year: 91

Plugging proposal received from: Tom Larson

Company: N.C.R.A. Phone: _____

Were: 8 5/8" set @ 174', 5 1/2" set at 3800', Top of cement 3300',
PBTD 3764' - 3494' - 3685', Holes in casing. Dakota to anhy.
Order 700 sx. 65/35 poz. - 10% gel.
Halliburton Cement Company. Express Well Service - DWS Water Truck.
Opened A-K zones. Test swab. P & A.

Received
10/11/91

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 1:00P.M., Day: 1, Month: October, Year: 91

Actual plugging report: Ran tubing to 2012'. Displaced 100 sx.
cement blend with 400# hulls mixed in. Laid down to 1200'. Displaced
100 sx. cement blend with 400# hulls mixed into circulate to surface.
Laid down tubing, squeezed 5 1/2 with total 320 sx. To Max. P.S.I.
500#. Close in P.S.I. 500#. Squeezed 8 5/8" with 100 sx.
To Max. P.S.I. 300#. Close in P.S.I. 300#.

Remarks: _____

INVOICED

I observed the plugging.

Carl Goodrow

DATE 11-14-91

INV. NO. 33705

Phil S.

(agent)

Form CP-2/3