

4- 062596

3-16
15-065-02913-00-00

127
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 6-11-50

NE SE NW /4 SEC. 17 , 09 S, 21 W
3630 feet from S section line
2970 feet from E section line

Operator license# 5363

Lease Cooley well #B#6

Operator: Berexco, Inc.

County Graham

121.84

Address: Box 723
Hays, Kansas
913-628-6101

Well total depth 3749 feet P.B.3635'
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 159 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Berexco, Inc. License# 5363

Address: Box 723, Hays, Kansas 67601

Company to plug at: Hour: 11:00A.M Day: 16 Month: March Year: 92

Plugging proposal received from: Ted Crawford

Company: Berexco, Inc. Phone: 913-628-6101

Were: Ordered 450 sks. of 60/40 posmix - 8% gel. and 5 sks. hulls.

3/26/92
MAR 26 1992

Plugging Proposal Received by: Gilbert G. Scheck
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 3:30P.M., Day: 16, Month: March, Year: 92

Actual plugging report: 8 5/8" @ 159' w/100 sks. 5 1/2" @ 3740'
w/75 sks. Top perf. @ 3430'. Pump in 2 3/8" tubing 3600'. Pulled
all 2 3/8" tubing. Hooked on to 5 1/2" and squeezed to 650 P.S.I.
w/220 sks. cement.

Max. pressure on 5 1/2" - 650 P.S.I. Shut in @ 400 P.S.I.
Max. pressure on backside - 200 P.S.I. Shut in @ 150 P.S.I. w/100
hulls. Total sacks 390 cement.

Remarks: Shot holes at 980' and 1730'.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2200 GL

INVOICED

I did / did not[] observe the plugging.

Gilbert G. Scheck

DATE 3-27-92

INV. NO. 34852

40

(agent)