

3-12
4- 070990

15-065-02916-00-00

67
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1-5-51

NE SW NE /4 SEC. 17 , 09 S, 21 W
3630 feet from S section line
1650 feet from E section line

Operator license# 5363

Lease Cooley well # B#10

Operator: Berexco, Inc.

County Graham

Address: Box 723
Hays, Kansas 67601
Ted Crawford

Well total depth 3728 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 164 feet

121.16

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License#

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 12 Month: March Year: 92

Plugging proposal received from: George Jorgensen

Company: Berexco, Inc. Phone: 913-628-6101

Were: 8 5/8" 164' S.P. cwc. w/80 sx. cement. 5 1/2" casing set @ 3721' w/75 sx. cement. Perf's @ 3924' to 3424'. C.I.B.P. @ 3692'. Casing good. Proposal 400 sx. 65/35 posmix - 8% gel - 5 sx. hulls. Spot with tubing at a minimum of 3000'. Run tubing to 3000'. Spot and displace cement. Load 5 1/2" casing from bottom to top, also load 5 1/2" x 8 5/8" annulus with cement. Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 3:15P.M., Day: 12, Month: March, Year: 92

Actual plugging report: Berexco Inc. ordered 400 sx. 65/35 pozmix - 8% gel. - 5 sx. hulls. Pumped in with pump truck, spotted and displaced cement through tubing. 1) 2 3/8" tubing @ 3608' spotted and displaced 150 sx. cement w/3 sx. hulls mixed in. 2) 2 3/8" tubing @ 1608' spotted and displaced 120 sx. cement w/2 sx. hulls mixed in. Cement circulated out of 5 1/2" casing. 3) Squeezed annulus w/100 sx. cement. Max. pressure 400 P.S.I. Shut in 300 P.S.I. 4) Squeezed 5 1/2" casing w/30 sx. cement. Max. pressure 400 P.S.I. Shut in @ 200 P.S.I.

Remarks: Cemented by B.J. Services.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES NO
Bottom plug(in place): YES X , CALC , NO X Dakota plug: YES X , NO
Plugged through TUBING X , CASING . Elevation: GL

I did [X] / did not [] observe the plugging.

DATE 4-7-92

INV. NO. 34873

Marion J. Schmidt
(agent)