

4-032064

6-23 15-065-02906-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API number: 15- - N/A

NE NW SW /4 SEC. 17, 09 S, 21 W
2310 feet from S section line
4290 feet from E section line

Operator license# 5363

Lease: Cooley Well # A-6

Operator: Berexco, Inc.

County: Graham 124.93

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 3844 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 180 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 23 Month: June Year: 1995

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 350 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Order work string.

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1995
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:30 P.M., Day: 23, Month: June, Year: 1995

Actual plugging report: 8 5/8" set at 180' w/125 sxs cwc. 5 1/2" set at 3824' w/75 sxs.
Squeezed at 2278' - 3109' w/200 sxs. 1126' - 1156' w/90 sxs. 1116' - 1126' w/350 sxs.
P.B.T.D. 3797'. Prod. Perfs 3568' - 3570'. Ran tubing to 3786' - displaced 75 sxs cement
blend. Pulled tubing to 2786' - displaced 75 sxs cement blend. Pulled tubing to 1786'
circulated with 110 sxs cement blend. Pulled tubing. Squeezed 5 1/2" with total of 300 sxs
cement blend with 500# hulls. Mixed into Max. P.S.I. 500#. Close in P.S.I. 200#. Squeezed
8 5/8" with 50 sxs cement blend to Max. P.S.I. 500#. Close in P.S.I. 200#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO
Plugged through TUBING, CASING. Elevation: GL

INVOICED
I did not observe the plugging.

Carl Goodrow
(agent)

DATE 7-19-95
INV. NO. 43113