

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02905-00-00
Spot: CSWNESW Sec/Twnshp/Rge: 17-9S-21W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: COOLEY A Well Number: 5
County: GRAHAM Total Vertical Depth: 3814 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: 8 1/2 3-96
Surface Casing: Size 8.62 feet: 175 125 SX CMT
Production: Size 5.5 feet: 3806 75 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/28/2002 11:00 AM

Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.

Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 270 sxs 60/40 pozmix - 10% gel - 500# hulls.
Casing leak 2801' - 2141' - squeeze with 300 sxs.
Casing leak 1700' - squeeze with 270 sxs.
Lock set at 3750'.
Packer 2945'.
Lock set at 2937'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/28/2002 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Berexco RIH with tubing to 2937' - pumped 50 sxs 60/40 pozmix with 200# hulls.
Pulled tubing to 1806' - pumped 120 sxs with 300# hulls to circulate cement.
Pulled tubing and tied onto casing - pumped 15 sxs 60/40 pozmix with Max. P.S.I. 800#. S.I.P. 650#.
Tied onto backside and pumped 85 sxs 60/40 pozmix with Max. P.S.I. 100#. S.I.P. 0#.
Plug complete.

RECEIVED
JAN 31 2002
KCC WICHITA

RECEIVED
JAN 31 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY - TICKET #10438.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE Feb 1-02

INV. NO. 2002061329

Form CP-2/3

JAN 29 2002

17-9-21W
SW NE SW

PALMER OIL CORPORATION ET AL #5 COOLEY A

Contr. PALMER OIL CORP. GRAHAM County

E 2313²² Comm. 1-2-50 Comp. 1-28-50 IP 300 BOPD

Tops	Depth	Datum	Casing
ANH	1796	+517	8" 175 ACID 500
			5" 3806
HEEB	3467	-1154	
LANS	3504	-1191	
SIMP	3799	-1486	
ARB	3806	-1493	
TD	3814	-1501	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

