

6 031417

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229Operator: Phillips Pet Co.Name & Address Route 3 Box 20AGreat Bend, Ks. 67530Abandoned Oil Well xx Gas Well Input Well SWD Well D&A Other well as hereinafter indicated Plugging Contractor KelsoAddress Chase, Ks.Company to plug at: Hour: PM Day: 13 Month: Sept Year: 19 90Plugging proposal received from Millard(company name) Kelso (phone) were: 10 3/4 set at 240 w/240 sks 6" set at 3809 w/300 sks Perf:3476 - 3817. Order 400 sks 65/35 poz 10% gel 500 lbs. hulls. Allied Cement Co.B and L Water truck. Keller water truck. Order 400 sks 65/35 poz 10% gel 500 lbs. hullsAllied Cement Co. Shots at 2000 to 1000. Could not pull pipe.Plugging Proposal Received by Carl
(TECHNICIAN)Plugging Operations attended by Agent?: All xx Part None Operations Completed: Hour: 4:30PM Day: 13 Month: Sept Year: 19 90ACTUAL PLUGGING REPORT Sq backside w/75 sks cement blend communicated
with 6" tied onto 6" and sq 6" and 10 3/4 w/total of 325 sks cement blend w/500 lbs.hulls mixed into max psi 600 lbs. Close in psi 300 lbs.

RECEIVED
STATE CORPORATION COMMISSION
10-3-90
OCT 3 1990

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Cut off head weld on plate.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-8-90INV. NO. 29554Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow