

15-065-01484-00-00

6-25 4-110047

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 12-12-43

NW NW SE /4 SEC. 23 , 09 S, 21 W
2310 feet from S section line
2310 feet from E section line

RECEIVED
JUL 13 1998
7-13-98
CONSERVATION DIVISION
Wichita, Kansas

Operator license# 30606
Operator: Murfin Drilling Company, Inc.
Address: 250 N. Water - #300
Wichita, Kansas 67202

Lease: Hinman Well # 2
County: Graham 123.57
Well total depth 3802 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1646 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 12:00 P.M. Day: 25 Month: June Year: 1998

Plugging proposal received from: John Gerstner

Company: Murfin Drilling Company, Inc. Phone: 316-267-3241

Were: According to KCC Rules & Regulations.
Plug while pulling casing.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 4:00 P.M., Day: 25, Month: June, Year: 1998

Actual plugging report: 8 5/8" set at 1646' with 650 sxs cement. 5 1/2" casing at 3791' w/125 sxs cement. Spotted sand and 5 sxs cement on bottom with dump bailer. Tied to 5 1/2" casing and pumped 28 sxs gel with 300# hulls, followed by 80 sxs cement and 200# hulls. Pulled to 1000' and pumped 26 sxs cement. Pulled to 275' and circulated with 34 sxs cement. Total of 140 sxs Mid-Conn II cement, 28 sxs gel and 500# hulls. Anhydrite at 1745'.

Remarks: Halliburton Cementing.
Condition of casing (in hole): GOOD X BAD
Bottom plug (in place): YES, CALC X, NO
Plugged through TUBING, CASING X.
Anhy. plug: YES X NO
Dakota plug: YES X, NO
Elevation: 2285 GL

I did [X] / did not [] observe the plugging.

Roger B. Moses
(agent)

INVOICED


DATE JUL 14 1998

INV. NO. 50919

GULF OIL CORP #2 HINMAN 23-9-21W NW NW SE
 Contr. _____ GRAHAM County
 E. 2285 Comm 11-11-43 Comp. 12-12-43 IP 3000 BOPD
 SONIC

Tops	Depth	Datum
ANH	1745	
LANS	3494	
B/KC	3717	
ARB	3741	
TD	3802	

Casing
 5" 3791
 Swb 104 BO/6 hrs
 A/2000
 300' OIH/1 hr
 1500' OIH/7 hrs
 2500' OIH/21 hrs
 2850' OIH/26 hrs



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS