

6 070392

API NUMBER 15- 065-22, 230-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE-SW-SW, SEC. 23, T. 9, S. R. 21 (W)

990 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8942

Lease Name Lewis Well # 1

Operator: V. F. Oil Company

County Graham 125.94

Name & Address: P.O. Box 1053

Well Total Depth 3875 feet

Hays, Kansas 67601

Conductor Pipe: Size 0 feet

Doug Van Loenen

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated Tag # 1697

Plugging Contractor Mohawk Drilling Inc License Number 6394

Address Great Bend, Kans. 67530

Company to plug at: Hour: 2:00 PM Day: 21st Month: Sept Year: 1985

Plugging proposal received from Ed Philbin

(company name) Mohawk Drilling Inc (phone) 913-628-2495

were: 8 5/8" 200 # SP. CUC w/ 60/40 Pozmix 2% Gel - Ca-Cl (By allied Int.)

Order 210 5th 60/40 Pozmix 3% Gel - Ca-Cl - 1 5th Cello and 8 5/8" Plug

spotted with Drill Stem, Reconditioned well (viscosity) heavy mud between plugs.

No circulation, Eto, 2319, only 1764, No Circulation Parting.

Mud Conductivity 45 Viscosity, 10" weight, water no gas.

Plugging Proposal Received by Maurus Schmidt
DOIC (TECHNICIAN)

Plugging Operations attended by Agents: All _____ Part _____ None

Operations Completed: Hour: 3:15 PM Day: 21st Month: Sept Year: 1985

ACTUAL PLUGGING REPORT Ordered 210 5th 60/40 Pozmix 6% Gel - Ca-Cl - 1 5th Cello 9" 8 5/8" Plug

spotted with Drill Stem, Reconditioned Well heavy mud between all plugs

1st Plug @ 1775 ft w/ 30 5th cont, 2nd Plug @ 1040 FT w/ 100 5th cont w/ 1 cello

3rd Plug @ 240 FT w/ 50 5th cont, 4th Plug Solid Bridge @ 40 5th cont w/ 10 5th

10 5th In Rat Hole (circulate) 10 5th IN Mouse Hole (circulate)

Cemented by allied Int.

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

DATE OCT 03 1985

INV. NO. 10352

RECEIVED STATE CORPORATION COMMISSION

SEP 30 1985

9-30-85 CONSERVATION DIVISION
Wichita, Kansas

Signed Maurus Schmidt
DOIC (TECHNICIAN) 9-27-85